

SUBMISSION DRAWINGS	
FOR APPROVAL AND STAMPING	
Architect	Registered Society
DTP (HQ)	DTP (R)
Assistant Architect	DTP (HQ)
(Dinesh Kumar) PA(HQ)	

NOTES:
1. All fixture provided in toilets are as per N.B.C.
2. Basement will be mechanically ventilated.
3. All spaces (parking basement, services basement etc.) Will be artificially lit.
4. Standby generating capacity will be provided for the electrical requirement of the total scheme. This therefore includes standby generation for all common services, fire services, lifts etc. And also the entire electrical load for the ventilation.
5. Fire safety measures as per NBC includes smoke detector, heat detector, sprinkler spacing is compliance with code.
6. All internal walls are 200mm and all internal walls are 100mm thick. (Valid for all drawings)

ZONE SECTOR 81 (R) DIVISION				
S.No.	DESCRIPTION	PERMISSIBLE AREA	PROPOSED AREA	
1	SITE AREA	14.20625 Acres (7,86,103.50 Sq.Mtr)		
	Residential Site Area @95%	13.496 Acres (5.46 Acres)		
	Commercial Site area @5%	0.71 Acres		
2	FAR as per TOD	2.63 (additional FAR 1.13 on payment basis)	2,06,980.23 (2,68,115.84 Sq.Mtr)	2.63
		1.13 (additional FAR 1.13 on payment basis)	88,918.87 (88,918.87 Sq.Mtr)	
	COMMERCIAL FAR	5.00% of FAR	10,465.12 Sq.Mtr	5.00%
	RESIDENTIAL FAR	95% of FAR	1,97,706.05 Sq.Mtr	95.000%
	Total	100.00%	2,08,171.17 Sq.Mtr	
3	GREEN AREA	15% of the area	3,423.56 Sq.Mtr	16.752%
4	GROUND COVERAGE	40% of the area	34,454.64 Sq.Mtr	45.48%
5	EWS Units	10% of Total no. of Units	232 Units	232.00 Units

S.No.	DESCRIPTION	No. Of Units	FAR (IN SQ. M)	NON FAR (IN SQ. M)	TOTAL BUA (IN SQ. M)	NO. OF FLOORS	TOTAL HEIGHT (in Mtrs)
1	Tower-01 (3BHK C+, & 3BHK C)	205.00	22,677.15	6,465.37	29,142.52	Podium + 25 floors	108
2	Tower-02 (2BHK C+ & 3BHK C)	198.00	14,566.21	4,202.87	18,769.08	Podium + 25 floors	108
3	Tower-03 (4BHK C)	195.00	21,132.96	6,166.20	27,299.16	Podium + 34 floors	105.05
4	Tower-04 (3BHK C+ & 2BHK C)	198.00	14,566.21	4,172.18	18,737.49	Podium + 25 floors	108
5	Tower-05 (3BHK C+ & 4BHK C+)	199.00	20,018.41	6,060.09	27,078.98	Podium + 35 floors	108
6	Tower-06 (3BHK C & 4BHK C+)	142.00	25,804.17	5,028.73	30,832.90	Podium + 36 floors	110.95
7	Tower-07 (3BHK C+)	135.00	19,400.41	5,014.30	24,414.71	Podium + 36 floors	105.05
8	Tower-08 (3BHK C & 4BHK C)	143.00	25,804.17	5,028.73	30,832.90	Podium + 36 floors	110.95
9	Tower-09 (3BHK C)	131.00	17,813.85	5,094.89	22,908.74	Podium + 34 floors	105
	TOTAL	1,514.00	3,86,885.62	51,181.87	2,38,067.24		
10	EWS	233.00	6,315.27	1,548.11	7,863.38	Service floor+17 floors	65.05
11	School	-	4,674.30	515.04	4,854.34	G+3 floors	
12	Commercial & Retail	-	10,938.75	1,311.96	12,830.52	G+33	47.95
13	Community building	-	3,643.27	611.51	3,874.78	G+2	13.5
14	Ancillary Areas (Guard Rooms, Driver Rooms/Toilets)	-	17.50	-	-	-	-
	TOTAL	1,747.00	2,06,390.22	57,699.91	2,68,090.05		

Density & Population Calculation			
	no of units	persons per unit	Total Population
Population of main units @5 persons	1,514	5	6,570.00 people
Population of Units with Service personnel @3persons	233	3	264.00 people
Population of EWS	233	3	699.00 people
Total Population			7,533 Nos.
Density Achieved			546.81 PPA

PARKING CALCULATION BREAKDOWN								
S.No.	DESCRIPTION	TYPE OF UNITS	No. of Units	Carpet Area / Qty in sqm	Parking Requirement as per TOD		Parking Provided as per TOD	Total proposed
	RESIDENTIAL				Eco/Dev	Total ECS		
1	Tower 01	3BHK C	35	139.00	35.00	3.5	98.0	3.5 105.00
		3BHK C+	5	142.00	10.00	2.0	19.5	2.0 39.00
	Tower 02	3BHK C	35	70.00	85.00	3.5	35	3.5 105.00
		3BHK C+	35	69.00	97.44	3.5	14.5	5.0 145.00
	Tower 03 (with service personnel)	3BHK C	34	132.00	123.00	3.0	3.0	7.0 129.00
	Tower 03			3.00	106.79	1.0	9	5.0 15.00
1	Tower 04	3BHK C+	35	98.00	56.48	3.5	43.5	5.0 143.00
		3BHK C	35	98.00	56.97	3.5	35	5.0 140.00
	Tower 05	3BHK C+	35	98.00	98.45	7.0	34.5	5.0 241.00
		4BHK C	35	70.00	100.03	3.0	70	5.0 250.00
	Tower 06 & 08	3BHK C	36	142.00	137.73	3.0	142	3.0 710.00
		4BHK C	36	142.00	139.37	3.0	142	5.0 710.00
	Tower 07	3BHK C+	35	135.00	113.32	3.0	126	5.0 671.00
	Tower 09	3BHK C	34	135.00	135.57	3.0	135	5.0 675.00
	TOTAL			1,514.00			1,130	2.00 4,558.00
	GRC			233.00				233.00
	Grand Total			1,547.00				5,599.00
2	EWS	5% of the total parking requirement		30 ECS				
3	COMMERCIAL AND RETAIL	1 ECS for 70 sqm of carpet area		110 ECS				
4	VISITOR PARKING	5.00% of the total parking requirement		111 ECS				
5	SCHOOL 1) Primary-cum-Nursery School + 1 Nursery School	15% of the area as per school (Primary-cum-Nursery School +0.5 Acres + Nursery School +0.2 Acres) i.e. 0.7 Acres	2,802.79	425 SQ.MTS				

PROPOSED PARKING CALCULATIONS							
S.No.	DESCRIPTION	AREA	SERVICE AREA	PARKING AREA	Per ECS Area considered	No. of ECS achieved in basement and podium level	No. of Actual Car Parks
1	RESIDENTIAL						
A	LOWER BASEMENT, B2	38,397.28	8,042.86	30,354.43	30	949	950
B	UPPER BASEMENT, B1	38,397.28	9,434.07	28,963.22	32	905	720
C	PODIUM LIVEL	21,355.76		21,355.76	28	770	765
	TOTAL	98,150.33	17,476.93	80,673.41		2,623	2,435
2	SURFACE PARKING ACHIEVED			1,625.74	23	71	63
						2,693	2,498
3	COMMERCIAL						
A	LOWER BASEMENT, B2 - Cellr stair	2,480.51	647.00	1,833.51	32	115	29
	Parking area due to stairs			3,007.02			289
B	UPPER BASEMENT, B1 - Full steps	2,480.51	881.24	1,799.27	32	227	57
	Parking area due to stairs			5,075.54			317
	TOTAL	4,961.02	1,528.24	7,289.80		226.42	100.00
4	VISITOR PARKING (@10% OF THE TOTAL PARKING REQUIRMENT)			3,401.79	23	148	111
5	EWS PARKING			1,299.74	23	56	58

Amenities & Infrastructure			
1 No. Nursery school about 2100 persons	1 Primary-cum-Nursery School + 1 Nursery School for 7300 persons	Total FAR provided for School	0.70
1 No. of Primary-cum-Nursery School above 5000 persons			

Site Considered for School	Site area in acres	Site area in sqm	FAR	FAR area to be used
1 No. of Primary-cum-Nursery School	0.5	2023.43	1.5	3035.15
1 No. Nursery School	0.2	809.37	1.5	1214.057
Total				4249.207

GROUND COVERAGE		
	AREA	PERCENTAGE
PODIUM LEVEL	29,886.972	80.58%
EWS & SCHOOL	1112.58	3.00%
COMMERCIAL	1,373.235	3.75%
Total	25161.587	45.23%

Checked and found ok for Public Health, External Service only subject to comments in the forwarding letter for [illegible]

Chief Engineer (HQ)
for Chief Engineer
HSVP, Panchkula

SANCTIONED
TO BE READ WITH THIS OFFICE
MEMO NO.:
DATED :

ARCHITECT
MORPHOGENESIS
41, Industrial Estate, Okhla Phase - III,
New Delhi 110020
TEL: 91 11 41626070
E Mail: studio@morphogenesis.org

CONSULTANT FOR ARCHITECTURAL PLANNING
WHITBY WOOD

CONSULTING MEP
PROION

CONSULTING LANDSCAPE ARCHITECT
MORPHOGENESIS
41, Industrial Estate, Okhla Phase - III,
New Delhi 110020
TEL: 91 11 41626070
E Mail: studio@morphogenesis.org

KEY PLAN

PROJECT
Proposed building plan for Mixed Land Use Colony (95% Residential and 5% Commercial) under TOD policy over an area measuring 14.20625 acres in the revenue estate of village Hayatpur Sector-81, Gurugram being developed by Godrej Properties Ltd.
(Lic No.163 of 2023 Dated 20-07-2023)

DEVELOPER
Godrej Properties Ltd.

DEVELOPER'S SIGNATURE :

For Godrej Properties Ltd.
Authorised Signatory

AUTHORIZED SIGNATORY

ARCHITECT'S SIGNATURE :

SAID V
CA/2010/49182

DRAWING NAME
SITE LAYOUT

DRAWING NO.
S-01

SCALE 1:500
DATE 09.10.2023